


Video and Audio in HDTV Studios




Principles and Choices
in
The new facilities for Danish Broadcasting
in Copenhagen

Model of the new DR facilities in Copenhagen



Segment 2 with main studios for TV production



What it looks like today



TV studios with control rooms

Facilities for Main Stream Production in segment 1

ST 5, Audience studio 720 m²
ST 6, Radio/TV studio 300 m²
ST 9A & 9B, Tandem Studio 2
each 140m²



Facilities for News and Sport in segment 2

ST 13, Newsroom studio 120m²
ST 14, Magazine studio 290m²



The HD evolution in Danish Broadcasting

- ▶ HD was not on the agenda when detailed planning of the new DR Green field site started in 2000
- ▶ But Test reports from SVT/IRT in 2002 revealed that introduction of flat panel displays in the home
 - > might force broadcasters to deliver pictures with improved resolution to the audience.
- ▶ DR decided in 2003 to add HD as an option in the tenders for studio equipment
 - > and partly equip the SDI infrastructure for HD-SDI.
- ▶ DR decided in 2005 to use the HD option
 - > for as many TV studios as possible within the budget limitations
- ▶ Today, no one doubts
 - > that this choice was necessary

The most important Tasks today

► To Finish

- > Integration of server based main stream production with Media Archive
- > metadata introduction from Ingest to distribution

► But also

- > Prepare new Studio installations for HD production
- > Establish SDI infra structure for HD
 - To gain experience with studio HD production

*The theme for
this presentation*


► And later on to

- > extend the IT based production system to handle HD also


In due time --this will also handle HD

Principles for IT-based TV- Production in DR

Version 10 September 2005



The target is: Same Work-Flow for SD and HD





The choices in the studio installations with focus on HD equipment

ST 5 week 43 The 720m2 --- not quite ready



**Camera
cables with
2 optical
fibers**

HD Cameras

- ▶ Cameras: 17 HD/SD cameras (Sony HDC-1500) has been purchased
 - > 8 big studio HD lenses and 11 ENG type (Canon)



- ▶ Camera cables: according to SMPTE 311 M with 2 optical fibers and wires for power supply ect.



- ▶ Viewfinders:
 - > Only a few pieces in color



Initial experience from HD Camera tests

- ▶ All 17 HD cameras has been tested and accepted in Copenhagen
- ▶ Some CCU units are still missing
- ▶ Lenses are important.
 - > the first tests with a borrowed EFP type lens limited the HD resolution
 - > later delivery of a new generation lenses were ok
- ▶ HD Test charts are difficult to get.
 - > We finally received one from DSC Laboratories in Canada
- ▶ Manuals are still missing

The production control room ST5



Equipment in Production Control Room for ST 5

- ▶ Video mixer: Software upgradeable for HD, and same brand in all TV studios (S&W)
 - > 48 inputs and 40 outputs
 - > 4 DVE (3D - 2channels)

- ▶ Monitoring: based on 3 pc of 70" rear projection units (Barco).
 - > A few inputs are for HD

- ▶ CGN is Viz-Trio
- ▶ Video Recording equipment ?



One of the Monitor Units



Size:
70 inch

Format:
4:3

Resolution:
1280x1024

Delay:
1+1/2 frame

CCU Control Room for ST5



Equipment for CCU Control room ST5

- ▶ Monitor wall with 4:3 CRT's
 - > Underscan for 16:9 production
- ▶ Only one multi-format monitor for HD
- ▶ CCU equipment for 8 camera channels
 - > extension to 12 is possible
 - > SD and HD output
 - > HD selectable 720p or 1080i
- ▶ Lightning control



The Audio Control Room ST5



Equipment in the Audio Control Room ST5

- ▶ Audio desk (SSL C200) with
 - > 64 channel strips
 - > 128 DSP channels
- ▶ All picture monitors are flat panels for SD
- ▶ Speakers are Dynaudio AIR series
- ▶ Production tool is Avid Pro Tools for 64 channels
 - > PC based ! (not MAC)
- ▶ Multichannel 5.1 audio can be produced simultaneous with stereo
- ▶ Finished production will be stored in the Media Archive as separate 24bit linear PCM files
- ▶ Multichannel audio will be distributed as Dolby Digital in DTT network (for SD and HD)
- ▶ Lip sync obtained by delay unit system



HD makes no difference !

Equipment Racks

- ▶ Special coax cables and patch panels for HD



- ▶ Video measuring equipment for SD/HD (Tektr. WVR 7100)



- ▶ Video router, Xenon
 - > partly for HD
- ▶ Tri-level sync system for HD and black burst for SD





The choices for the SDI and HD-SDI Infra structure with focus on HD equipment


SDI and HD-SDI Infrastructure

- ▶ All Audio "embed and de-embed" equipment are for SDI and HD-SDI, and with 8 audio channels
 - ▶ All transmitters and receivers for optical fibers are for SD and HD
 - ▶ Coax cables are made special for HD and can run 100 meters
- More than 200 km has been installed




- ▶ BNC 75 ohm connectors are special for HD
- ▶ Routers are partially equipped with cross points for HD
- ▶ TX routers (32x32) are for HD

Principles for SDI and HD-SDI infrastructure



Long haul optical connections for SD/HD

- ▶ Optical tie-lines with RX/TX units between Studio routers



The choices for HD production standard


The choice for Production standards

- ▶ The HDTV production standard will be 720p/50 according to SMPTE 296M-2001 (This will also be the DTT distribution standard)
- ▶ HD film-style drama production may be in the 1080p/25 standard according to SMPTE 274-1998

SMPTE 296M-2001
Revision of
ANSI/SMPTE 296M-1997

SMPTE STANDARD

for Television — 1280 × 720 Progressive Image Sample Structure — Analog and Digital Representation and Analog Interface


 Page 1 of 14 pages

Contents

- 1 Scope
- 2 Normative references
- 3 General
- 4 Timing
- 5 System colorimetry
- 6 Raster structure
- 7 Digital representation
- 8 Digital timing reference sequences (SAV, EAV)
- 9 Ancillary data
- 10 Bit-parallel interface
- 11 Analog sync
- 12 Analog interface
- Annex A Production aperture
- Annex B Pre- and post-filtering characteristics
- Annex C Bibliography

1 Scope

1.1 This standard defines a family of progressive image sample systems for the representation of stationary or moving two-dimensional images sampled temporally at a constant frame rate and having an image format of 1280 pixels by 720 lines and an aspect ratio of 16:9 as given in table 1. All systems in the table have the common characteristic that all the samples gathered within a single temporal unit, a frame, shall be spatially contiguous and provide a complete description of that frame (4.2). This standard specifies:

- R'G'B' color encoding;
- R'G'B' analog and digital representation;
- Y'P_bP_r color encoding, analog representation, and analog interface; and
- Y'C_bC_r color encoding and digital representation.



Table 1 – Image sampling systems

	System nomenclature	Luma or R'G'B' samples per active line (S/L)	Active lines per frame (AL/F)	Frame rate, Hz	Luma or R'G'B' sampling frequency (fs), MHz	Luma sample periods per total line (S/TL)	Total lines per frame
1	1280 × 720/60	1280	720	60	74.25	1650	750
2	1280 × 720/59.94	1280	720	60/1.001	74.25/1.001	1650	750
3	1280 × 720/60	1280	720	60	74.25	1980	750
4	1280 × 720/30	1280	720	30	74.25	3300	750
5	1280 × 720/29.97	1280	720	30/1.001	74.25/1.001	3300	750
6	1280 × 720/25	1280	720	25	74.25	3960	750
7	1280 × 720/24	1280	720	24	74.25	4125	750
8	1280 × 720/23.98	1280	720	24/1.001	74.25/1.001	4125	750

NOTE – For systems 4 through 8, analog video interface is not preferred. See clause 12.

Installation of the IT system in parallel

- ▶ Remember the IT based (SD) production environment




CAT 6 data cabling

Storage area for equipment



The digital evolution at DR



Production plans



**Show-time
for the first SD production
in the big studio 5 will be
21. of January 2006**

All production studios running with SD from week 07-2006 !

Production plans



**Show-time
for the first HD production
in the big studio 5
is not yet decided**

Buildings in "DR Byen" summer 2005



Thank you for the attention